



ALTERNATE 'A2' - Direct drain water to Detroit Edison Co. Picked by natural waterway

DETROIT EDISON CO.

MICHIGAN AIR LINE RAILWAY (GTW RR)

18" VINYL CLAD CYCLOPEL FENCE WITH CLIMBING AND PLANTING

DE CO TOWER

FUTURE ADDITION

Heavy Duty Automobile Parking

12" THICK CONCRETE ROAD SLAB-TYPE

PROPOSED TERMINAL BUILDING

PAVING

EXIST. GRADE-TYP

5' HIGH LIGHT STANDARD (4 HEADS / 2100)

2" CONC. CURB (4' HIGH) - ALL AS PARTIAL LOCALITY STRCS

ESTIMATED INSTALLATION COSTS FOR MAJOR UTILITIES & PAVING
 PAVING (BOARDFORD) - 30,000
 STORM SEWER - 7,250
 SANITARY SEWER - 4,750
 TOTAL - 42,000

ALTERNATE 'A2'
 EXTEND EAST 34' WIDE 6" THICK CONCRETE PAVING APPROX 70'
 TO MEET CITY SPECIFICATIONS

FERRY AVE - 70'

PLAINFIELD AVE

SITE PLAN
 SCALE - 1" = 50'

PROPOSED TERMINAL FACILITIES		FIG 14 1971
BOARDFORD AVE	PONTIAC, MICH.	4710
GLS LEASCO INC.		ENGINEER
34200 GROUND RD.	STILLING HTS, MICH.	JOB NO
SITE PLAN		7/1/75
TRADE-WISE ENGINEERING CO.		SHT NO
		11